

Dr. JAYANTHI. M, I.F.S., MEMBER SECRETARY

STATE LEVEL ENVIRONMENT IMPACT ASSESSMENT AUTHORITY-TAMILNADU

3rd Floor, Panagal Maaligai, No.1 Jeenis Road, Saidapet,Chennai-15.

Phone No: 044-24359973 Fax No: 044-24359975

ENVIRONMENTAL CLEARANCE (EC)

Letter No. SEIAA/TN/F. 6397 /EC/ 8(b)/620/2018 dated: 31.12.2018.

To.

M/s. Cybercity Builders and Developers Pvt Ltd,

No. 123/1, Mangadu,

Kundrathur Main Road,

Chennai-600122.

Sir.

Sub: SEIAA, TN - Environmental Clearance – Expansion of Residential development project by M/s. Cybercity Builders & Developers Pvt I td at Survey Numbers: 765/29B2C, 765/29B1, 389/2, 384, 398/2, 397/2, 390, 391, 392, 380 & 379 of Mangadu village, Pallavaram taluk, Kanchipuram District, Tamil Nadu - Category – "B1" and Schedule δ. No. 8(b) - Issued - Regarding.

Ref: 1. Lr.No.SEIAA/TN/F.5120/EC/8(a)/502/2016 dated 10.11.2016.

2. Lr.No.SEIAA/TN/F.6397/EC/8(a)/535/2017 dated 13.09.2017.

3. Lr.No.SEIAA/F.No.6397/2018/8(b)/ToR-373/2018 dated 23.05.2018.

Page 1 of 25



- 4. EIA report submitted by the project proponent for Environment Clearances dated 04.07.2018.
- 5. Minutes of the 116th SEAC meeting held on 09.07.2018.
- 6. The Proponent submitted reply on 07.08.2018.
- 7. Minutes of the 333rd SEIAA Meeting held on 29.11.2018.
- 8. The Proponent submitted reply on 07.12.2018.
- 9. Minutes of the 335th SEIAA Meeting held on 31.12.2018.

This has reference to your application 4th cited, the proposal is for obtaining Environmental Clearance to establish a building and construction project under Category B1 and Schedule S.No. 8(b) under the Environment Impact Assessment Notification, 2006, as amended.

The Competent Authority and Authorized signatory furnished detailed information in Form 1 and Form 1A and liquidate enclosures are as Annexures:

Annexure 1

	PROJECT	PROJECT DETAILS	
SL No	Description -	Details	
1)	Name of the Project proponent	M/s. Cybercity Builders and Developers	
	and address	Pvt Ltd,	
		No. 123/1, Mangadu,	
		Kundrathur Main Road,	
		Chennai-600122.	
2)	Proposed Activity	Proposed expansion of Residential	
		Development project	
3)	Schedule No.	8(b)	
4)	Project Location		
	i)Survey No	765/29B2C, 765/29B1, 389/2, 384,	
		398/2, 397/2, 390, 391, 392, 380 & 379	
	ii)Revenue Village	Mangadu Village	

Page 2 of 25

3 1 DEC 2018

THE STATE OF	iii)Taluk	Pallavaram
	iv)District	Kancheepuram
5)	Area of the Land	108816.72 Sq.m
6)	Built up Area	In already Approved EC- 1,27,801.39
		Sq.m
		After expansion- 3,62,934.25 Sq.m
7)	Brief description of the project	Expansion of Residential development
	(After Expansion)	comprises of
		Phase I: Row houses with G+2 floors
		with amenity building with G+2 floors
	AND STATE OF THE S	(234 DU)
		Phase II: 2 towers consist of two
		basements with Ground + 19 Floors
		each and a club house (G+1) (820 DU)
- 4 - 1	the thirt of the same of the same	Phase III: 3 basements (combined
	Service of the servic	basement) with tower 1, 2 and 3 (G+19
		floors) with club house I (G+2 floors)
1000	CO MARKET	and 3 basements (combined basement)
	Doctor	with tower 6,7 and 8 (G+19 floors) with
W		club house III (G+2 floors) (1560 DU)
#C		Total Built up area: 3,62,934.25 Sqm
8)	Expected Occupancies (After	14289 Nos
	Expansion)	
9)	Parking facilities (After	91717.81 Sq.m
	Expansion)	
10)	Green Belt(After Expansion)	17490.36 sq.m
11)	UTILITIES-WATER	The state of the s
	(After Expansion)	186,000
	Total Fresh Water Requirements	1201 KLD

Page 3 of 25



	a)Source from where the water is	Ground water or Mangadu Panchayat
	proposed to be drawn	
1.7	i)Domestic Purposes	1188 KLD
	ii) Swimming Pool	13 KLD
	iii) Toilet Flushing(Recycled Water)	624 KLD
	iv) Green belt development/gardening (Recycled Water)	61 KLD
	v) OSR (Recycled Water)	37 KLD
	vi) CMWSSB STP	887 KLD
12)	Waste Water (After Expansion)	
111	i)Sewage	1694 KLD
	ii) Details of Treatment	STP capacity: 1820 KLD (70 KLD+100 KLD+550 KLD+650 KLD+450 KLD each 1 No)
	iii) Mode of Disposal with quantity	Treated Sewage: Toilet Flushing – 624 KLD, Greenbelt development - 61 KLD OSR Gardening- 37 KLD Excess treated sewage to CMWSSB STP- 887 KLD
13)	SOLID WASTE (After Expansion)	
A	I) Municipal solid Waste	8054 Kg/day
	i) Bio degradable – 4832.4 Kg /day	Organic Waste Convertor
	ii) Non Bio degradable – 3221.6	Disposed to Authorized Recyclers

Page 4 of 25



	Kg /day	
	iii) STP Sludge – 232 Kg /day	Manure for gardening
14)	POWER REQUIREMENT	
	(After Expansion)	
1	i) Electricity Board	12250 KVA
	ii) D.G. Set	1 nos. of 250 KVA with stack height of
	iii) Height of Stack above the	13.6 m from GL
	tallest Building	2 nos. of 400 KVA with stack height of
		66.2 m from GL
		7 nos. of 500 KVA with stack height of
		66.67 m from GL
15)	Project Cost (For expansion)	After Expansion- Rs. 458.42 Crores
		(Project Cost for Approved EC:
		Rs. 157.04 Crores)
16)	EMP Cost (After Expansion)	For Construction:
		Capital Cost – 54 Lakhs,
		For Operation Phase:
	WHALLE	Capital Cost – 729 Lakhs,
	TIN THE STATE OF T	Operation cost- 149 Lakhs
-		

Annexure 2- Affidavit

The Proponent has furnished affidavit in Fifty Rupees stamp paper attested by the Notary stating that

We commit to SEIAA that the total fresh water requirement for our proposed project is 1201 KLD and it will be met through Ground water and alternate source will be Mangadu Panchayat. We assure that the required permission from the competent Authority for supply of fresh water for entire period of operation will be obtained before handing over to the occupants.

Page 5 of 25



The Total quantity of Treated wastewater generated from the above is 1694 KLD, out of which 624 KLD will be utilized for flushing, 61 KLD for greenbelt development (The treated water used for greenbelt development inside the project premises will not pollute the soil/ground water/adjacent canals/lakes/ponds etc) and 37 KLD of treated wastewater will be used for OSR area and the remaining 887 KLD of excess treated sewage will be discharged into CMWSSB STP.

Total Solid waste generated from the proposed development is 8054 kg/day; Out of which 7794 kg/day of biodegradable waste will be treated in organic waste convertor within the project site. 260 kg/day of Non biodegradable waste will be sold to recyclers. STP sludge of 232 kg/day will be used as Manure for greenbelt development.

We assure we are liable for the operation and maintenance of STP for 10 years from the date of operation of the project

We also assure that the storm water drain would not carry any untreated (or) treated sewage.

We also assure that the proposed site does not encroach nearby water bodies/reserve forest/wetlands

We assure that for CER, out of 229.21 Lakhs, an amount of Rs 129.21 Lakhs shall be deposited to Environmental Management Authority of Tamil Nadu (EMAT), Department of Environment for the purpose of tree plantation and maintenance in Chennai before obtaining CTO from TNPCB. The remaining 100 Lakhs will be spent for infrastructure facilities to the below mentioned Schools nearby Government schools (Construction and renovation of Classrooms, Toilets, compound walls, sports facilities) before obtaining CTO from TNPCB

S. No	Name of the Government School
1	Mangadu Government School
2	Government Girls High School, Kovoor
3	Government School, Walaja Street
4	Government High School, Mangadu Main Road
5	Government School, Kundrathur Road

Page 6 of 25



And also aware that I can be prosecuted under relevant act and rules, if am not ensuring the adherence of the above commitment.

The project activity is covered in 8(a) of the Schedule and is of B2 category. It does not require Public Consultation as per Para 7 III Stage (3) (i) (d) of EIA Notification, 2006.

The Authority after consideration all the requisite documents with status and data and based on SEAC appraisal and recommendations for issue of Environmental Clearance in its 116th meeting held on 09.07.2018, SEIAA placed the proposal in the 335th SEIAA meeting held on 31.12.2018, hereby conveyed Environmental Clearance along with the conditions containing four parts namely

Part - A -Common conditions applicable for Pre-construction,
Construction and Operational Phases

Part - B - Specific Conditions - Pre construction phase

Part - C - Specific Conditions - Construction phase

Part - D - Specific Conditions - Operational Phase/Post constructional Phase / Entire life of the project.

Validity:

The SEIAA hereby accords Environmental Clearance to the above project under the provisions of EIA Notification dated 14th September, 2006 as amended, with validity for Seven years from the date of issue of EC, subject to the compliance of the terms and conditions stipulated below:

Page 7 of 25



SPECIFIC CONDITIONS

The Environmental Clearance shall not be cited for relaxing the other applicable rules to this project.

<u>Part - A - Common conditions applicable for Pre-construction,</u> <u>Construction and Operational Phases:</u>

- 1. Any appeal against this environmental clearance shall lie with the Hon'ble National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.
- The construction of STP, Solid Waste Management facility, E-waste management facility, DG sets, etc., should be made in the earmarked area only. In any case, the location of these utilities should not be changed later on.
- 3. The Environmental safeguards contained in the application of the proponent /mentioned during the presentation before the State Level Environment Impact Assessment Authority / State Level Expert Appraisal Committee should be implemented in the letter and spirit.
- 4. All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire and Rescue Services Department, Civil Aviation Department, Forest Conservation Act, 1980 and Wild Life (Protection) Act, 1972, State / Central Ground Water Authority, Coastal Regulatory Zone Authority, other statutory and other authorities as applicable to the project shall be obtained by project proponent from the concerned competent authorities.
- 5. The SEIAA reserves the right to add additional safeguard measures subsequently, if non-compliance of any of the EC conditions is found and to take action, including revoking of this Environmental Clearance as the case may be.

Page 8 of 25



- A proper record showing compliance of all the conditions of Environmental Clearance shall be maintained and made available at all the times.
- 7. The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company. The status of compliance of environmental clearance conditions and shall also be sent to the Regional Office of the Ministry of Environment and Forests, Chennai by e-mail.
- 8. The Regional Office of the Ministry located at Chennai shall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer (s) of the Regional Office by furnishing the requisite data / information / monitoring reports.
- 9. "Consent for Establishment" shall be obtained from the Tamil Nadu Pollution Control Board and a copy shall be submitted to the SEIAA, Tamil Nadu.
- 10. In the case of any change(s) in the scope of the project, a fresh appraisal by the SEAC/SEIAA shall be obtained before implementation.
- 11. The conditions will be enforced inter-alia, under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, the Public Liability Insurance Act, 1991, along with their amendments ,draft Minor Mineral Conservation & Development Rules , 2010 framed under MMDR Act 1957, National Commission for protection of Child Right Rules ,2006 and rules made there under and also any other orders passed by the Hon'ble Supreme Court of India/Hon'ble High Court of Madras and any other Courts of Law, including the Hon'ble National Green Tribunal relating to the subject matter.

Page 9 of 25

3 1 DEC 2018

- 12. The Environmental Clearance shall not be cited for relaxing the other applicable rules to this project.
- 13. Failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of the Environment (Protection) Act, 1986.
- 14. The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, Chennai, the respective Zonal Office of CPCB, Bengaluru and the TNPCB. The criteria pollutant levels namely; PM10, PM2.5, SO2, NOx (ambient levels as well as stack emissions) or critical sectoral parameters, indicated for the project shall be monitored.
- 15. The SEIAA, TN may cancel the environmental clearance granted to this project under the provisions of EIA Notification, 2006, if, at any stage of the validity of this environmental clearance, if it is found or if it comes to the knowledge of this SEIAA, TN that the project proponent has deliberately concealed and/or submitted false or misleading information or inadequate data for obtaining the environmental clearance.
- 16. The Environmental Clearance does not imply that the other statutory / administrative clearances shall be granted to the project by the concerned authorities. Such authorities would be considering the project on merits and be taking decisions independently of the Environmental Clearance.
- 17. The SEIAA, TN may alter/modify the above conditions or stipulate any further condition in the interest of environment protection, even during the subsequent period.
- 18. The Environmental Clearance does not absolve the applicant/proponent of his obligation/requirement to obtain other statutory and administrative clearances from other statutory and administrative authorities.

Page 10 of 25



- 19. Where the trees need to be cut, compensation plantation in the ratio of 1:10 (i.e. planting of 10 trees for every one tree that is cut) should be done with the obligation to continue maintenance.
- 20.A separate environmental management cell with suitable qualified personnel should be set-up under the control of a Senior Executive who will report directly to the Head of the Organization and the shortfall shall be strictly reviewed and addressed.
- 21. The EMP cost of Rs. 729 Lakhs shall be deposited in a Nationalized bank by opening separate account and the head wise expenses statement shall be submitted to TNPCB with a copy to SEIAA annually.
- 22. The proponent has to obtain NOC from the PWD for the drawal of ground water or the proponent has to find alternate proposal for sourcing the water outside (Mangadu Panchayat), for this effect the proponent has to furnish the commitment letter from Mangadu Panchayat before issue of CTO.
- 23. The proponent should maintain play area of 3000 sq.m as committed.
- 24. A fire alarm system should be installed and maintained as committed.
- 25. Solar energy saving shall be increased to atleast 5% of total energy utilization.
- 26. Towards green belt, the project proponent has allotted 17490.36 sq.m (16.07%). Green belt shall be planted with 1360 numbers of indigenous species. The following species shall be planted.

Pongamia glabra	Pungan
Thespesia populnea	Poovarasu
Ficus religiosa	Arasu
Ficus glomerata	Athi
Azadirachta indica	Vembu
Terminalia arjuna	Neermarudhu

Page 11 of 25

3/1 DEC 2018

Calophyllum inophyllum	Punnai
Syzygium cumini	Naval
Madhuca longifolia	Ilippai
Mimusops elengi	Magilam

- 27. For CER: The project proponent shall allocate and utilize the CER fund of Rs. 229.21 Lakhs (0.5% of the project cost Rs. 458.42 crores). The schedule for utilization of CER funds is as follows:
 - a) Out of Rs. 229.21 Lakhs, an amount of Rs. 129.21 Lakhs shall be deposited to Environmental Management Authority of Tamil Nadu (EMAT), Department of Environment for the purpose of tree plantation and maintenance in Chennai before issue of CTO from TNPCB.
 - b) The remaining Rs. 100 Lakhs shall be spent for infrastructure facilities in 3-5 nearby Government schools (construction and renovation of classrooms, toilets, compound walls, sports facilities) before obtaining CTO from TNPCB.
- 28. The Project Proponent has to provide rain water harvesting collection tank to the capacity of 1100 cu.m in order to recover and reuse the rain water during normal rains.
- 29. The proponent shall develop the green belt as per the plan furnished and area earmarked for the greenbelt shall not be alter at any point of time for any other purpose.
- 30 The proponent should strictly comply with, Tamil Nadu Government Order (Ms) No.84 Environment and forests (EC.2) Department dated 25.06.2018 regarding ban on one time use and throwaway plastics irrespective of thickness with effect from 01.01.2019 under Environment (Protection) Act, 1986.

Page 12 of 25



Part - B - Specific Conditions - Pre construction phase:

- 1. The project authorities should advertise with basic details at least in two local newspapers widely circulated, one of which shall be in the vernacular language of the locality concerned, within 7 days of the issue of clearance. The press releases also mention that a copy of the clearance letter is available with the State Pollution Control Board and also at website of SEIAA, TN. The copy of the press release should be forwarded to the Regional Office of the Ministry of Environment and Forests located at Chennai and SEIAA-TN.
- 2. In the case of any change(s) in the scope of the project, a fresh appraisal by the SEAC/SEIAA shall be obtained before implementation.
- 3. A copy of the clearance letter shall be sent by the proponent to the Local Body. The clearance letter shall also be put on the website of the Proponent.
- 4. The approval of the competent authority shall be obtained for structural safety of the buildings during earthquake, adequacy of fire fighting equipments, etc as per National Building Code including protection measures from lightning etc before commencement of the work.
- 5. All required sanitary and hygienic measures for the workers should be in place before starting construction activities and they have to be maintained throughout the construction phase.
- 6. Design of buildings should be in conformity with the Seismic Zone Classifications.
- 7. The Construction of the structures should be undertaken as per the plans approved by the concerned local authorities/local administration.
- 8. No construction activity of any kind shall be taken up in the OSR area.
- 9. Consent of the local body concerned should be obtained for using the treated sewage in the OSR area for gardening purpose. The quality of treated sewage shall satisfy the bathing quality prescribed by the CPCB.

Page 13 of 25



MEMBER SECRETARY

- 10. The height and coverage of the constructions shall be in accordance with the existing FSI/FAR norms as per Coastal Regulation Zone Notification, 2011.
- 11. The Project Proponent shall provide car parking exclusively for the visiting guest in the proposed residential apartments as per CMDA norms.
- 12. The project proponent shall ensure the level of basement shall be above maximum flood level.
- 13. The proponent shall prepare completion plans showing Separate pipelines marked with different colours with the following details
 - i. Location of STP, compost system, underground sewer line.
 - ii. Pipe Line conveying the treated effluent for green belt development.
 - iii. Pipe Line conveying the treated effluent for toilet flushing
 - iv. Water supply pipeline
 - v. Gas supply pipe line, if proposed
 - vi. Telephone cable
 - vii. Power cable
 - viii. Strom water drains, and
 - ix. Rain water harvesting system, etc.,. and it shall be made available to the owners
- 14.A First Aid Room shall be provided in the project site during the entire construction and operation phases of the project.
- 15. The structural design of the proposed building must be vetted by premier academic institutions like Anna University, IIT Madras, etc., and the fact shall be informed to SEIAA.
- 16. The present land use surrounding the project site shall not be disturbed at any point of time.
- 17. The Provisions of Forest conservation Act 1980, Wild Life Protection Act 1972 & Bio diversity Act 2002 should not be violated.

Page 14 of 25

3 1 DEC 2018

Part - C - Specific Conditions - Construction phase:

1. Construction Schedule:

 The Project proponent shall have to furnish the probable date of commissioning of the project supported with necessary bar charts to SEIAA-TN.

2. Labour Welfare:

- i) All the labourers to be engaged for construction should be screened for health and adequately treated before and during their employment on the work at the site.
- ii) Personnel working in dusty areas should wear protective respiratory devices and they should also be provided with adequate training and information on safety and health aspects. Occupational health surveillance program of the workers should be undertaken periodically to observe any contradictions due to exposure to dust and take corrective measures, if needed.
- iii) Periodical medical examination of the workers engaged in the project shall be carried out and records maintained. For the purpose, schedule of health examination of the workers should be drawn and followed accordingly. The workers shall be provided with personnel protective measures such as masks, gloves, boots etc.

3. Water Supply:

- i) The entire water requirement during construction phase may be met from ground water source from the source with approval of the PWD Department of water resources/ may be out sourced.
- ii) Provision shall be made for the housing labour within the site with all necessary infrastructures and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.

Page 15 of 25

3 1 DEC 2018

- iii) Adequate drinking water and sanitary facilities should be provided for construction workers at the site. The treatment and disposal of waste water shall be through dispersion trench after treatment through septic tank. The MSW generated shall be disposed through Local Body and the identified dumpsite only.
- iv) Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices prevalent.
- v) Fixtures for showers, toilet flushing and drinking water should be of low flow type by adopting the use of aerators / pressure reducing devises / sensor based control.

4. Solid Waste Management:

- i) The solid waste in the form of excavated earth excluding the top soil generated from the project activity shall be scientifically utilized for construction of approach roads and peripheral roads, as reported.
- ii) In the solid waste management plan, the STP sludge management plan for direct use as manure for gardens is not acceptable; it must be co-composted with biodegradables.
- iii) House hold hazardous waste such as batteries, small electronics, CFL bulbs, expired medicines and used cleaning solvent bottles should be segregated at source, collected once in a month from residences and disposed as per the SWM rules 2016.

5. Top Soil Management:

i) All the top soil excavated during construction activities should be stored for use in horticulture/ landscape development within the project site.

6. Construction Debris disposal:

 Disposal of construction debris during construction phase should not create any adverse effect on the neighboring communities and

Page 16 of 25

3 1 DEC 2018

be disposed off only in approved sites, with the approval of Competent Authority with necessary precautions for general safety and health aspects of the people. The construction and demolition waste shall be managed as per Construction & Demolition Waste Management Rules, 2016.

ii) Construction spoils, including bituminous materials and other hazardous materials, must not be allowed to contaminate watercourses. The dump sites for such materials must be secured so that they should not leach into the adjacent land/ lake/ stream etc.

7. Diesel Generator sets:

- i) Low Sulphur Diesel shall be used for operating diesel generator sets to be used during construction phase. The air and noise emission shall conform to the standards prescribed in the Rules under the Environment (Protection) Act, 1986, and the Rules framed thereon.
- ii) The diesel required for operating stand by DG sets shall be stored in underground tanks fulfilling the safety norms and if required, clearance from Chief Controller of Explosives shall be taken.
- iii) The acoustic enclosures shall be installed at all noise generating equipments such as DG sets, air conditioning systems, cooling water tower etc.

8. Air & Noise Pollution Control:

- i) Vehicles hired for bringing construction materials to the site should be in good condition and should conform to air and noise emission standards, prescribed by TNPCB/CPCB. The vehicles should be operated only during non-peak hours.
- ii) Ambient air and noise levels should conform to residential standards prescribed by the TNPCB, both during day and night. Incremental pollution loads on the ambient air and noise quality

Page 17 of 25

3 1 DEC 2018

- should be closely monitored during the construction phase. The pollution abatement measures shall be strictly implemented.
- iii) Traffic congestion near the entry and exit points from the roads adjoining the proposed project site shall be avoided. Parking shall be fully internalized and no public space should be utilized. Parking plan to be as per CMDA norms. The traffic department shall be consulted and any cost effective traffic regulative facility shall be met before commissioning.
- iv) The buildings should have adequate distance between them to allow free movement of fresh air and passage of natural light, air and ventilation.

9. Building material:

- i) Fly-ash blocks should be used as building material in the construction as per the provision of Fly ash Notification of September, 1999 and amended as on 27th August, 2003 and Notification No. S.O. 2807 (E) dated: 03.11.2009.
- ii) Ready-mix concrete shall alone be used in building construction and necessary cube-tests should be conducted to ascertain their quality.
- iii) Use of glass shall be reduced up to 40% to reduce the electricity consumption and load on air conditioning. If necessary, high quality double glass with special reflecting coating shall be used in windows.

10. Storm Water Drainage:

- i) Storm water management around the site and on site shall be established by following the guidelines laid down by the storm water manual.
- ii) Storm water management plan shall be obtained by engaging the services of Anna University/IIT.

Page 18 of 25



11. Energy Conservation Measures:

- i) Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material, to fulfill the requirement.
- ii) Opaque wall should meet prescribed requirement as per Energy Conservation Building Code which is mandatory for all air conditioned spaces by use of appropriate thermal insulation material to fulfill the requirement.
- iii) All norms of Energy Conservation Building Code (ECBC) and National Building Code, 2005 as energy conservation have to be adopted Solar lights shall be provided for illumination of common areas.
- iv) Application of solar energy should be incorporated for illumination of common areas, lighting for gardens and street lighting. A hybrids system or fully solar system for a portion of the apartments shall be provided.
- v) A report on the energy conservation measures conforming to energy conservation norms prescribed by the Bureau of Energy Efficiency shall be prepared incorporating details about building materials & technology; R & U factors etc and submitted to the SEIAA in three month's time.
- vi) Energy conservation measures like installation of CFLs/TFLs for lighting the areas outside the building should be Integral part of the project design and should be in place before project commissioning.

12. Fire Safety:

i) Adequate fire protection equipments and rescue arrangements should be made as per the prescribed standards.

Page 19 of 25



ii) Proper and free approach road for fire-fighting vehicles upto the buildings and for rescue operations in the event of emergency shall be made.

13. Green Belt Development:

- i) The Project Proponent shall plant tree species with large potential for carbon capture in the proposed green belt area based on the recommendation of the Forest department well before the project is completed.
- ii) Towards green belt, the project proponent has allotted 17490.36 sq.m (16.07%). Green belt shall be planted with 1360 numbers of indigenous species. The following species shall be planted.

17 to 12 Carlo 12 Car	
Pongamia glabra	Pungan
Thespesia populnea	Poovarasu
Ficus religiosa	Arasu
Ficus glomerata	Athi
Azadirachta indica	Vembu
Terminalia arjuna	Neermarudhu
Calophyllum inophyllum	Punnai
Syzygium cumini	Naval
Madhuca longifolia	Ilippai
Mimusops elengi	Magilam
	l.

14. Sewage Treatment Plant:

i) The Sewage Treatment Plant (STP) installed should be certified by an independent expert/ reputed Academic institutions for its adequacy and a report in this regard should be submitted to the SEIAA, TN before the project is commissioned for operation.

Page 20 of 25



Explore the less power consuming systems viz baffle reactor, etc., for the treatment of sewage.

ii) The Proponent shall install STP as furnished. Any alteration to satisfy the bathing quality shall be informed to SEIAA-TN.

15. Rain Water Harvesting:

- i) The proponent/ Owner of the Flats shall ensure that roof rain water collected from the covered roof of the buildings, etc shall be harvested so as to ensure the maximum beneficiation of rain water harvesting by constructing adequate sumps so that 100% of the harvested water shall be reused.
- ii) Rain water harvesting for surface run-off, as per plan submitted should be implemented. Before recharging the surface run off, pretreatment with screens, settlers etc. must be done to remove suspended matter, oil and grease, etc. The Proponent shall provide 90 numbers of rain water recharging pit. The bore wells / percolation pits/ etc. for rainwater recharging should be kept at least 5 mts. above the highest ground water table.
- iii) The Project Proponent has to provide rain water harvesting collection tank to the capacity of 1100 cu.m in order to recover and reuse the rain water during normal rains.

16. Building Safety:

Lightning arrester shall be properly designed and installed at top of the building and where ever is necessary.

<u>Part - D - Specific Conditions - Operational Phase/Post constructional phase/Entire life of the project:</u>

1. There should be Fire fighting plan and all required safety plan.

3 1 DEC 2011

- 2. Regular fire drills should be held to create awareness among owners/ residents.
- 3. House hold hazardous waste such as batteries, small electronics, CFL bulbs, expired medicines and used cleaning solvent bottles should be

Page 21 of 25

- segregated at source, collected once in a month from residences and disposed as per the SWM rules 2016.
- 4. The building should not spoil the green views and aesthetics of surroundings and should provide enough clean air space.
- The proponent has informed that the excess treated sewage of 887 KLD will be discharged into the CMWSSB Network. Hence, the proponent has to get necessary permission from CMWSSB before obtaining CTO from TNPCB.
- 6. The swimming pool top up water which will be discharged once in 3 months should be scientifically managed without causing ground water pollution.
- 7. Solar energy saving shall be increased to atleast 5% of total energy utilization.
- 8. For CER: The project proponent shall allocate and utilize the CER fund of Rs. 229.21 Lakhs (0.5% of the project cost Rs. 458.42 crores). The schedule for utilization of CER funds is as follows:
 - i) Out of Rs. 229.21 Lakhs, an amount of Rs. 129.21 Lakhs shall be deposited to Environmental Management Authority of Tamil Nadu (EMAT), Department of Environment for the purpose of tree plantation and maintenance in Chennai before issue of CTO from TNPCB.
 - ii) The remaining Rs. 100 Lakhs shall be spent for infrastructure facilities in 3-5 nearby Government schools (construction and renovation of classrooms, toilets, compound walls, sports facilities) before obtaining CTO from TNPCB.
- 9. The EMP cost of Rs. 729 Lakhs shall be deposited in a nationalized bank by opening separate account and the head wise expenses statement shall be submitted to TNPCB with a copy to SEIAA annually.

Page 22 of 25



- 10 The EMP cost shall be printed in the Brochure / Pamphlet for the preparation of the sale of the property and should also mention the component involved.
- 11. The Project proponent shall get due permission from the wetland Authority before the commencement of the work, if applicable.
- 12. The project activities should in no way disturb the manmade structures .
- 13. The Proponent shall do afforestation/ restoration programme contemplated to strengthen the open spaces shall preferably include native species along with the financial forecast for planting and maintenance for 5 years.
- 14. "Consent to Operate" should be obtained from the Tamil Nadu pollution Control Board before the start of the operation of the project and copy shall be submitted to the SEIAA-TN.
- 15. Raw water quality to be checked for portability and if necessary RO plant shall be provided.
- 16. The Proponent should be responsible for the maintenance of common facilities including greening, rain water harvesting, sewage treatment and disposal, solid waste disposal and environmental monitoring including terrace gardening for a period of 3 years. Within one year after handing over the flats to all allottees a viable society or an association among the allottees shall be formed to take responsibility of continuous maintenance of all facilities with required agreements for compliance of all conditions furnished in Environment Clearance (EC) order issued by the SEIAA-TN or the Proponent himself shall maintain all the above facilities for the entire period. The copy of MOU between the buyers Association and proponent shall be communicated to SEIAA-TN.
- 17. The ground water level and its quality should be monitored and recorded regularly in consultation with Ground Water Authority.
- 18. Treated effluent emanating from STP shall be recycled / reused to the maximum extent possible. The treated sewage shall conform to the

Page 23 of 25

3 1 DEC 2018

- norms and standards for bathing quality laid down by CPCB irrespective of any use. Necessary measures should be made to mitigate the odour and mosquito problem from STP.
- 19. The Proponent shall operate STP continuously by providing stand by DG set in case of power failure.
- 20. It is the sole responsibility of the proponent that the treated sewage water disposed for green belt development/ avenue plantation should not pollute the soil/ ground water/ adjacent canals/ lakes/ ponds, etc
- 21. Adequate measures should be taken to prevent odour emanating from solid waste processing plant and STP.
- 22. The e waste generated should be collected and disposed to a nearby authorized e-waste centre as per E- waste (Management & Handling), Rules 2016 as amended.
- 23. Diesel power generating sets proposed as source of back-up power during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets.
- 24. The noise level shall be maintained as per MoEF/CPCB/TNPCB guidelines/norms both during day and night time.
- 25. Spent oil from D.G sets should be stored in HDPE drums in an isolated covered facility and disposed as per the Hazardous & other Wastes (Management & Transhoundary Movement) Rules 2016. Spent oil from D.G sets should be disposed off through registered recyclers.
- 26. The proponent is required to provide a house hold hazardous waste / E-waste collection and disposal mechanism.
- 27. The proponent/ Owner of the Flats shall ensure that storm water drain provided at the project site shall be maintained without choking or without causing stagnation and should also ensure that the storm water shall be properly disposed off in the natural drainage / channels without disrupting

Page 24 of 25

3 1 DEC 2018

the adjacent public. Adequate harvesting of the storm water should also be ensured.

- 28. Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination.
- 29.A copy of the Environmental clearance (EC) letter shall be made available to all the allottees along with the allotment order / sale deed.
- 30. Failure to comply with any of the conditions mentioned above may result in withdrawal of this clearance and attract action under the provisions of the Environment (Protection) Act, 1986.



MEMBER SECRETARY
SEIAA-TN

Copy to:

- 1. The Principal Secretary to Government, Environment & Forests Dept, Quyt, of Tamil Nadu, Fort St. George, Chennai - 9
- 2. The Chairman, Central Pollution Control Board, Parivesh Bhavan, CBD Cum-Office Complex, East Arjun Nagar, New Delhi 110032.
- 3. The Member Secretary, Tamil Nadu Pollution Control Board, 76, Mount Salai, Guindy, Chennai-600 032.
- 4. The APCCF (C), Regional Office, Ministry of Environment & Forest (SZ), 34, HEPC Building, 1st& 2nd Floor, Cathedral Garden Road, Nungambakkam, Chennai 34.
- Monitoring Cell, I A Division, Ministry of Environment & Forests,
 Paryavaran Bhavan, CGO Complex, New Delhi 110003.
- 6. The Commissioner, Greater Chennai Corporation, Rippon Building, Chennai
- 7. Stock File.



